	Title: Distribution Briefing Document for Contractors	
	Type: Non- Restricted\Manual	Page 1 of 5
Active Date:30 Mar 2021	Status:Active	Number: MAN-003
Review Date:31 Oct 2027	Owner: Baldacchino, Damian	Revision: 5

MAN-003

Distribution Briefing Document for Contractors

Last Review Details – Refer to QPulse for full history


Review Comments	Review Owner	Date
<QPulse_DocLastReviewDetails>	Baldacchino, Damian	31 Oct 2025

Latest Revision Details – Refer to QPulse for full history

Revision number	Revision Details
5	Added the national emergency number 112 and minor formatting changes.

Approval details for latest Revision

Approver	Date	Response
Magro, Emanuel	26 Mar 2021 8:21 am	Accept
Falzon, Michael	30 Mar 2021 7:15 am	Accept
Xuereb, Graziella	26 Mar 2021 1:41 pm	Accept
Baldacchino, Damian	29 Mar 2021 2:08 pm	Accept

	Title: Distribution Briefing Document for Contractors	
	Type: Non- Restricted\Manual	Page 2 of 5
Active Date:30 Mar 2021	Status:Active	Number: MAN-003
Review Date:31 Oct 2027	Owner: Baldacchino, Damian	Revision: 5

1 Site specific risks

Enemalta's sites are sensitive as part of the National Critical Infrastructure. The sites may also contain hazards such as high-voltage electricity, confined spaces, chemicals and fire risks.

Contractor's personnel are all expected to be aware of the risks involved in the maintenance of the plant. Safety helmets and safety shoes should be worn in all areas of the plant. Appropriate Personal Protective Equipment (PPE) should be worn according to the area you are in and in accordance to the work being carried out.

Enemalta plc is committed to maintaining the highest standards in order to safeguard the Health & Safety of its employees, contractors, visitors and third parties. All contractors and visitors are expected to fully comply with all regulations.

2 Emergency Reporting

In the event of a serious emergency (Fire / Injury/Environmental incident) contractor's personnel are to inform the Network Control Room. The Contractor's personnel are also to notify the National Emergency Services (Fire, Police, Ambulance) as necessary, on 112

Network Control Room	
Internal (PABX) phone	567/440
External or mobile phone	22980 567 / 22980 440
National Emergency Number	112

2.1 First Aid

Contractors are expected to provide their own first aid requirements unless specifically agreed otherwise.


First aid kits are available in Enemalta plc vehicles

Eyewash units are installed near the battery room and clearly marked or eye wash kits are available in Enemalta plc's vehicles.

In the event of any serious injury contact the Network Control Room and the National Emergency line 112.

2.2 Fire

In the event of a fire or other emergency condition the Project Manager should be informed. In the event of a fire starting in the contractor's area, the contractor should only attempt to extinguish the

	Title: Distribution Briefing Document for Contractors	
	Type: Non- Restricted\Manual	Page 3 of 5
Active Date:30 Mar 2021	Status:Active	Number: MAN-003
Review Date:31 Oct 2027	Owner: Baldacchino, Damian	Revision: 5

fire if this is small enough to be controlled by the fire fighting equipment on site. The Project Manager should also be notified.

In the event of any fire contact the Network Control Room and the National Emergency line 112.

If a fire alarm is raised, even if known to be accidental, ALWAYS inform the Project Manager and the NCR immediately.

Any use of fire equipment must be reported to the Project Manager who will in turn inform Health and Safety office.

2.3 Emergency Exits and Evacuation

All emergency exits and evacuation routes are marked using European standard signage (Green Exit signs). (Appendix) Escape routes are fitted with emergency lighting.

2.4 Assembly points

Emergency Assembly Points are situated outside all major installations marked by the sign (Appendix)

2.5 Reporting

After any incident on Enemalta site, the contractor must submit a written report to the Project Manager

3 Smoking

All Enemalta sites are non-smoking. Smoking is only allowed in designated areas.

4 Driving Speed Limits


Any Contractors' vehicle entering Enemalta premises shall not exceed the 15km/hour speed limit, unless a lower limit is signposted. (Appendix)

5 Permit to Work

Enemalta operates a permit to work system. Any work on electrical systems requires a permit to work from the Project Manager.

5.1 Hot Work

Enemalta operates a hot work permit system. Before any hot work is carried out a hot work permit must be obtained from the Enemalta Project Manager

	Title: Distribution Briefing Document for Contractors	
	Type: Non- Restricted\Manual	Page 4 of 5
Active Date:30 Mar 2021	Status:Active	Number: MAN-003
Review Date:31 Oct 2027	Owner: Baldacchino, Damian	Revision: 5

6 Environmental Procedures

The contractor shall be familiar with Enemalta's **Waste Management (SOP-045)** and **Chemical Handling (SOP-044)** procedures. The procedures shall be explained to the contractor and a copy of these documents shall be forwarded to the contractor or his delegate. The latter shall confirm receipt of these documents by signing the relevant form **FRM-042 – Contractor's Briefing and Employee Training**.

6.1 Chemical/Oil Spills

Please care for the environment and prevent any spillages.

In case of a chemical or oil spill contact immediately the Network Control Room on (22980 567/22980 440) and the Project Manager and give clear indications as to the type and the whereabouts of the spill. Actions should be taken to control the spill in the shortest time possible. If use is made of absorbent material to control the spill this should be disposed of as hazardous waste according to instructions given by Project Manager, as per Enemalta Waste Management Procedure.


6.2 Hazardous Substances

Permission by the Project Manager is required to bring in chemicals or hazardous substances on site. A copy of the Safety Data Sheet (SDS) for the chemical or hazardous substance is to be forwarded to the Project Manager who will in turn forward it to the Health, Safety and Environmental Officer.

6.3 Waste Management

Contractor shall make arrangements with Enemalta for Waste collection and disposal PRIOR to commencement of works, waste is to be disposed of as per Enemalta Waste Management Procedure. Contractor needs to get written permission from Enemalta if an agreement is reached to use Enemalta's waste disposal facilities.

For further details please contact the Enemalta Project Manager.

	Title: Distribution Briefing Document for Contractors	
	Type: Non- Restricted\Manual	Page 5 of 5
Active Date:30 Mar 2021	Status:Active	Number: MAN-003
Review Date:31 Oct 2027	Owner: Baldacchino, Damian	Revision: 5

7 Appendix

